

## Evaluation Report "Grande Tile" Metal Roof Assembly

**Manufacturer:**  
**Green American Home**  
(A division of Isaiah Industries)  
8510 Industry Park Drive  
Piqua, OH 45356  
(800) 543-8938

*for*

**Florida Product Approval**

**# FL 14949.2 R3**

**Florida Building Code 7th Edition (2020)**

**Method: 1 - D**

**Category: Roofing**

**Sub - Category: Metal Roofing**

Product: "Grande Tile" Roof Panel  
Material: Aluminum  
Support: Wood Deck

### Prepared by:


James L. Buckner, P.E., SECB  
Florida Professional Engineer # 31242  
Florida Evaluation ANE ID: 1916  
Project Manager: Diana Galloway  
Report No. 20-240-GT-A4W-ER  
(Revises 17-130-GT-A4W-ER, FL14949.2 R2)  
Date: 10 / 01 / 20

### Contents:

Evaluation Report

Pages 1 – 9

This item has been electronically signed and sealed by James L. Buckner, P.E., on this date using a Digital Signature. Printed copies of this document are not considered signed and sealed, and the signature must be verified on any electronic copies.



A handwritten signature in blue ink, appearing to read "James L. Buckner".

2020.10.02 18:48:16 -04'00'

Manufacturer:	<b>Green American Home</b> (A division of Isaiah Industries) 8510 Industry Park Drive Piqua, OH 45356 (888) 705-5656 <a href="https://www.greenamericanhome.com/">https://www.greenamericanhome.com/</a>								
Product Name:	<b>Grande Tile</b>								
Product Category:	Roofing								
Product Sub-Category	Metal Roofing								
Compliance Method:	State Product Approval Rule 61G20-3.005 (1) (d)								
Product/System Description:	"Grande Tile" Aluminum roof panel, with a barrel tile appearance, mechanically attached to Wood Deck.								
Product Assembly as Evaluated:	Refer to Page 4 of this report for product assembly components/materials & standards:  <table><tr><td>1. Roof Panel</td><td>Grande Tile</td></tr><tr><td>2. Fasteners</td><td>#9 HWH Screws</td></tr><tr><td>3. Underlayment</td><td>Per Roofing Manufacturer's Guidelines</td></tr></table>			1. Roof Panel	Grande Tile	2. Fasteners	#9 HWH Screws	3. Underlayment	Per Roofing Manufacturer's Guidelines
1. Roof Panel	Grande Tile								
2. Fasteners	#9 HWH Screws								
3. Underlayment	Per Roofing Manufacturer's Guidelines								
Support:	<b>Type:</b> Wood Deck (Design of support and its attachment to support framing is outside the scope of this evaluation.)  <b>Description:</b> <ul style="list-style-type: none"><li>• 19/32" or greater plywood,</li><li>• or Wood plank (min. specific gravity of 0.42)</li></ul>								
Slope:	Minimum slope shall be In compliance with FBC Chapter 15 based on the type of roof covering, applicable code sections and in accordance with manufacturer's recommendations.								
Performance:	Wind Uplift Resistance: <ul style="list-style-type: none"><li>• Design Uplift Pressure: (Refer to "Table A" attachment details herein)</li></ul>								
		<b>METHOD 1: - 92 PSF</b>							
		<b>METHOD 2: - 107 PSF</b>							

**Performance Standards:**

The product described herein has demonstrated compliance with:

- UL 580-06 – *Test for Uplift Resistance of Roof Assemblies—with Revisions through February 1998*
- UL 1897-12 – *Uplift test for roof covering systems*
- TAS 125-03 – *Standard Requirements for Metal Roofing Systems*

**Standards Equivalency:**

The UL 580-94 & UL 1897-98 standard version used to test the evaluated product assembly is equivalent with the prescribed standards in UL 580-06 & UL 1897-12 adopted by the Florida Building Code 7th Edition (2020).

**Code Compliance:**

The product(s) described herein have demonstrated compliance with the performance standards listed above as referenced in the Florida Building Code 7th Edition (2020).

**Evaluation Report Scope:**

This building envelope product is evaluated for compliance with the structural wind load requirements of the Florida Building Code, as related to the scope section to Florida Product Approval Rule 61G20-3.001.

**Limitations and Conditions of Use:**

- Scope of "Limitations and Conditions of Use" for this evaluation:  
This evaluation report for "Optional Statewide Approval" contains technical documentation, specifications and installation method(s) which include "Limitations and Conditions of Use" throughout the report in accordance with Rule 61G20-3.005. Per Rule 61G20-3.004, the Florida Building Commission is the authority to approve products under "Optional Statewide Approval".
- Option for application outside "Limitations and Conditions of Use"  
Rule 61G20-3.005(1)(e) allows engineering analysis for "project specific approval by the local authorities having jurisdiction in accordance with the alternate methods and materials authorized in the Code". Any modification of the product as evaluated in this report and approved by the Florida Building Commission is outside the scope of this evaluation and will be the responsibility of others.
- This report is a building code product evaluation per FLPE rule (FAC) 61G15-36 to comply with Florida product approval rule (FAC) 61G20-3. This evaluation report is part of the Florida Building Commission approval for the listed code related criteria. This report by James Buckner, P.E. and CBUCK Engineering is not a design certification of code compliance construction submittal documentation, per FBC section 107, for any individual structure, site specific or permit design.
- All metal components and fasteners shall be corrosion resistant in accordance with applicable sections of FBC, including but limited to Sections 1504.3.2, 1506.5, 1506.6 and 1507.4.4.
- Design of support system is outside the scope of this report.
- Fire Classification is outside the scope of Rule 61G20-3, and is therefore not included in this evaluation.
- This evaluation report does not evaluate the use of this product for use in the High Velocity Hurricane Zone code section. (Dade & Broward Counties)

**Quality Assurance:** The manufacturer has demonstrated compliance of roof panel products in accordance with the Florida Building Code and Rule 61G20-3.0005 (3) for manufacturing under a quality assurance program audited by an approved quality assurance entity through **Farabaugh Testing & Engineering** (FBC Organization ID# QUA 7733)

**Components &  
Materials:  
(by Manufacturer)**

**Roof Panel:**

Material: Aluminum  
Thickness: 0.032" (min.)  
Panel Width: 44-1/4" nominal (max.) Coverage  
Rib Height: 1-5/8" nominal  
Tile Step: 13-3/4" nominal  
Alloy Type: 3105-H14  
Corrosion Resistance: Per FBC Section 1507.4.3

**Grande Tile**

**Fastener:**

Type: Hex Washer Head Screw w/WSW  
Size : #9 - 14 x 1-1/2" (or length to meet min. penetration)  
Min..Penetration thru Deck: 3/16" min.thru bottom of wood deck  
Corrosion Resistance: Per FBC Section 1506.6 and 1507.4.4  
Standard: Per ANSI/ASME B18.6.1

**Panel to Deck**

**Fastener:**

Type: Hex Washer Head Screw w/WSW  
Size : #9 - 14 x 2-1/2" (or length to meet min. penetration)  
Min..Penetration thru Deck: 3/16" min. thru bottom of wood deck  
Corrosion Resistance: Per FBC Section 1506.6 and 1507.4.4  
Standard: Per ANSI/ASME B18.6.1

**Panel to Panel, Side Lap Stitch & Thru Deck**

**Underlayment:**

Material and application shall be in compliance with FBC Section 1507.1.1 and in accordance with applicable code sections and manufacturer's recommendations.

**Installation:**

**Installation Method:**

(Refer to "TABLE A" below and drawings at the end of this evaluation report.)

- Attach panel to deck fasteners in tile step valleys, along the length of the panel and thru the wood deck.
- Attach panel to panel stitch fasteners at every tile step, along the length of the side laps and thru the wood deck.
- For panel construction at the end of panels, refer to manufacturer's instructions and any site specific design.

TABLE "A" ALLOWABLE LOADS		
	METHOD 1:	METHOD 2:
Design Pressure:	- 92 PSF	- 107 PSF
Row Fastener Spacing/Pattern:	See Detail "1" Same Every Row	See Details "2A" & "2B" Alternating Rows
Row Spacing:	13-3/4"	13-3/4"
Side Lap Stitching:	13-3/4" At every tile step	13-3/4" At every tile step
Notes: <ul style="list-style-type: none"><li>• Allowable design pressure(s) for allowable stress design (ASD).</li></ul>		


Install the "Grande Tile" roof panel assembly in compliance with the installation method listed in this report and applicable code sections of FBC 7th Edition (2020). The installation method described herein is in accordance with the scope of this evaluation report. Refer to manufacturer's installation instructions as a supplemental guide for attachment.

**Referenced Data:**

1. TAS 125-03 (Per UL 580 & UL 1897) Uplift Test  
By Hurricane Test Laboratories, LLC (FBC Organization# ID: TST 1527)  
Report # 0197-1110-05/0197-0417-06, Date: 2/19/07,
2. Quality Assurance  
By Farabaugh Testing & Engineering (FBC Organization ID# QUA 7733)
3. Equivalency of Test Standard Certification  
By James L. Buckner, P.E. @ CBUCK Engineering
4. Certification of Independence  
By James L. Buckner, P.E. @ CBUCK Engineering  
(FBC Organization # ANE 1916)

**Installation Method  
Green American Home  
"Grande Tile" (0.032" Alum) Roof Panel attached to Wood Deck**


**Drawings**




**Typical Panel Profile**

## Installation Method Green American Home "Grande Tile" (0.032" Alum) Roof Panel attached to Wood Deck

### METHOD 1:



### Detail "1" - Assembly Profile View (Typical Fastener Pattern Across Row)




Typical Roof Assembly Isometric View

**Installation Method**  
**Green American Home**  
**"Grande Tile" (0.032" Alum) Roof Panel attached to Wood Deck**

**METHOD 2:**




**Detail "2A" - Assembly Profile View**  
(Typical Fastener Pattern Across Alternate ODD Rows)



**Detail "2B" - Assembly Profile View**  
(Typical Fastener Pattern Across Alternate EVEN Rows)

**Installation Method  
Green American Home  
"Grande Tile" (0.032" Alum) Roof Panel attached to Wood Deck**

**METHOD 2:**



**Typical Roof Assembly Isometric View**

<b>TABLE "A"</b>		
<b>ALLOWABLE LOADS</b>		
	<b>METHOD 1:</b>	<b>METHOD 2:</b>
<b>Design Pressure:</b>	<b>- 92 PSF</b>	<b>- 107 PSF</b>
Row Fastener Spacing/Pattern:	See Detail "1" Same Every Row	See Details "2A" & "2B" Alternating Rows
Row Spacing:	13-3/4"	13-3/4"
Side Lap Stitching:	13-3/4" At every tile step	13-3/4" At every tile step